



DEPARTMENT OF THE NAVY
COMMANDER
NAVY REGIONAL MAINTENANCE CENTER
9170 SECOND STREET, SUITE 245
NORFOLK, VA 23511-2325

9000
C200/457
21 Oct 21

MEMORANDUM FOR RECORD

From: Director, NAVSEA Standard Specification for Ship Repair and Alteration Committee (SSRAC)

Subj: FISCAL YEAR 2023 NAVSEA STANDARD ITEMS

Ref: (a) COMUSFLTFORCOMINST 4790.3
(b) NAVSEAINST 9070.1

Encl: (1) NSI, 009-05, 009-73, 009-88 and 009-122 Summary of Change FY 23 CH-1

1. Per references (a) and (b), the Fiscal Year 2023 CH-1 (FY23 CH-1) NAVSEA Standard Items (NSI) are available on the official SSRAC Web site at:

<http://www.navsea.navy.mil/Home/RMC/CNRM/OurPrograms/SSRAC.aspx>

2. Rationale for Change: In the FY23 NSI initial release, two Category II NSIs were changed to Category I. The NSIs were not adequately updated to reflect this change causing confusion for planners on how to invoke specific steps if there is no longer an associated work item. There were also two previously released Category I NSIs discovered with the same problem. This change (FY23 CH1) updates these four Category I NSIs to eliminate the requirement to include specific steps in a work item.

3. The **FY-23 CH-1** NSIs are effective for availabilities in which FY-23 Standard Items are invoked. FY-23 availabilities that are not at the 100% of D Level Maintenance Work Package Lock Milestone must be planned to incorporate **FY-23 CH-1** NSIs listed. **FY-23 CH-1** NSIs must supersede all related MSWTs, CSWTs, SWTs, and LWTs.

FY-23 CH-1 NSIs Affected: 009-05, 009-73, 009-88 and 009-122 Summary of change in Enclosure (1)

- a. 009-05 Temporary Access; accomplish
- b. 009-73 Shipboard Electrical/Electronic Cable Procedure; accomplish
- c. 009-88 Collection, Holding and Transfer (CHT) and Motor Gasoline(MOGAS) Tanks, Spaces, and Piping, including Sewage or MOGAS-Contaminated Tanks, Spaces, and Piping; certify
- d. 009-122 Temporary Padeye; install and remove

Subj: FISCAL YEAR 2022 NAVSEA STANDARD ITEMS AND APPENDIX 4-E

4. Requests for deviations from this requirement must be submitted via e-mail and routed to CNRMC (C200) for adjudication and approval. A separate deviation request must be submitted for each availability and must fully explain the reason(s) for the deviation (i.e., why deviation is required, how planning would be affected, how availability would be impacted, etc).
5. SSRAC and RMC Coordinators are responsible for advising users within their command of this notice. Code 400 Contracts Department is responsible for advising Master Ship Repair (MSR) Contractors and Agreement for Boat Repair (ABR) Contractors under their cognizance of the availability of these products.
6. The requirements of this letter do not authorize any change in terms, conditions, delivery schedule, price, or amount of any Government contract. In the event you consider the requirements represent a change for which an equitable adjustment is in order, you are to advise the Contracting Officer of the particular technical or contractual requirements regarded as changed, and take no action with regard to such changed requirements until notified in writing of the Contracting Officer's response.
7. Point of Contact for further information is Mr. James A. Simmons, Technical Director, 757-400-0020, james.a.simmons3@navy.mil

J. A. SIMMONS

Copy To:
SSRAC email

NSI Summary of Change FY 23 CH-1

009-05 Temporary Access; accomplish

3.14.1 Deleted Accomplishment of welding, fabrication, and inspection requirements to support installation of a temporary access must be in accordance with NAVSEA Standard Items (See Note 4.2) **and changed to;**

3.14.1 Accomplish the requirements of 009-12 of 2.1 for welding, fabrication, and inspection requirements to support installation of a temporary access.

3.15 Deleted Accomplish a chalk test on structural closure in way of temporary access. ***In accordance with NAVSEA standard items. (See Note 4.3) and changed to;***

3.15 Accomplish the requirements of 009-25 of 2.1 for chalk test on each structural closure in way of temporary access.

3.16 Deleted 3.16 Accomplishment of structural boundary testing (e.g., cofferdam, vacuum box, air hose, water hose) of each watertight/airtight temporary access closure must be in accordance with NAVSEA standard items (See Note 4.3).**and changed to;**

3.16 Accomplish the requirements of 009-25 of 2.1 for structural boundary testing of each watertight/airtight temporary access closure (e.g. cofferdam, vacuum box, air hose, and water hose).

Deleted NOTEs 4.2 and 4.2;

4.2 If welding, fabrication, or inspection for installation of a temporary access of 3.14.1 is required; the use of Category II Standard Item 009-12 “Welding, Fabrication, and Inspection Requirements; accomplish” of 2.1 will be specified in the Work Item.

4.3 If a structural boundary test (e.g., ***chalk test***, cofferdam, vacuum box, air hose, water hose) to support testing of a watertight/airtight temporary access closure is required; the use of Category II Standard Item 009-25 “Structural Boundary Test; accomplish” of 2.1 will be specified in the Work Item.

009-73 Shipboard Electrical/Electronic Cable Procedure; inspect, test, install, remove, and repair

3.4.6 Deleted Accomplishment of local air hose tests after the installation, removal and relocation of cables of each new and disturbed multi-cable transit device, multi-cable penetrators, stuffing tubes, kick pipes, and cable penetrations of tightness boundaries must be in accordance with NAVSEA Standard items (See Note 4.8). **and changed to;**

3.4.6 *Accomplish the requirements of 009-25 of 2.1 for conducting a local air hose test after the installation, removal or relocation of cables of each new and disturbed multi-cable transit device, multi-cable penetration, stuffing tube, kick pipe, and cable penetration of tightness boundaries.*

New 3.10 *Accomplish the requirements of 009-32 of 2.1 for new and disturbed surfaces.*

Deleted NOTE 4.8;

4.8 If local air hose test of 3.4.6 is required, the use of Standard Item 009-25 of 2.1 “Structural Boundary Test; accomplish” will be specified in the Work item.

Deleted NOTE 4.9;

4.9 If cleaning and painting for new and disturbed surfaces are required; the use of Standard Item 009-32 of 2.1 “Cleaning and Painting Requirements; accomplish” will be specified in the Work Item.

009-88 Collection, Holding and Transfer (CHT) and Motor Gasoline (MOGAS) Tanks, Spaces, and Piping, including Sewage or MOGAS-Contaminated Tanks, Spaces, and Piping; certify

3.1.4 Deleted Accomplishment of a Process Control Procedure (PCP) to support a step-by-step procedure of how the certification process will be accomplished must be in accordance with NAVSEA Standard Items (See Note 4.4). **and Changed to;**

3.1.4 *Accomplish the requirements of 009-09 of 2.1 to support a step by step procedure of how the certification process will be accomplished.*

Deleted NOTE 4.4;

4.4 A PCP to support a step-by-step procedure of how the certification process will be accomplished is required; the use of Category II Standard Item 009-09 “Process Control Procedure (PCP); provide and accomplish” of 2.1 must be specified in the Work Item.

009-122 Temporary Padeye; install and remove

3.6 Deleted “Accomplishment of” and replaced with “*Accomplish*”.

3.6 *Accomplish the requirements of 009-32 of 2.1 for new and disturbed surfaces.*

Deleted NOTE 4.2;

4.2 If cleaning and painting of 3.6 is required, the use of Category II Standard Item 009-32 “Cleaning and Painting Requirements; accomplish” of 2.1 will be specified in the Work Item.